

**DEPARTMENT OF THE ARMY PERMIT**  
**Regional Permit 26**  
**Emergency Reconstruction and Repair Activities for Flood Damaged Areas**  
**in All Waters of the United States**  
**In the State of Illinois**

**Permittee:** General public meeting the terms and conditions herein.

**Number:** CEMVS-OD-F-2019-516(Regional Permit 26)

**Expiration Date:** May 15, 2022

**Issuing Office:** U.S. Army Corps of Engineers, St. Louis District  
1222 Spruce St.  
St. Louis, MO 63103-2833

You are authorized to perform work in accordance with the terms and conditions specified below.

**NOTE:** The term "you" and its derivatives, as used in this permit, means the permittee or any future transferee. The term "this office" refers to the appropriate district or division office of the Corps of Engineers having jurisdiction over the permitted activity or the appropriate official of that office acting under the authority of the commanding officer.

**Project Description.** Work is authorized to excavate and/or place fill material for protection and/or repair of existing flood damaged structures, damaged land areas and/or damaged fills as follows:

1. Repair of levees to pre-existing elevations and cross-section, including breach closures and borrow operations.
2. Bridge embankment protection (armoring) and/or repair.
3. Repair of pre-existing highway or railroad embankments and the addition or repair of stone (armoring) protection.
4. Repair of pre-existing utility protection structures.
5. Placement of rock and/or earth materials for stream or ditch bank protection and/or stream or ditch bank restoration.
6. Drainage channel/ditch restoration to pre-flood capacity and flow line unless the flow line must be altered due to other damage associated with the flood event.
7. Restoration of creek channels to pre-flooding alignment and capacity.
8. Construction of temporary haul roads and temporary fills to facilitate the completion of any of the listed activities.

Note: Maintenance of existing flood damaged structures and/or flood damaged fills, which have been previously authorized, may be authorized by Nationwide Permit No. 3 or exempted by Part 323.4 of Federal regulations 33 CFR 320-331. The repair of uplands damaged by storms, floods or other discrete events may be authorized by Nationwide Permit No. 45 upon notification and review by the appropriate Corps of Engineers District, Regulatory Branch.

**Project Location.** This Regional Permit will authorize work in waters of the United States (including rivers, lakes, streams and wetland areas) associated with emergency reconstruction and repair activities in counties declared flood disaster areas by the State of Illinois.

## **Permit Conditions:**

### **❖ General Conditions:**

1. The time limit for completing the work authorized ends 180 days from the date of each individual project determination. If you find that you need more time to complete the authorized activity, submit your request for a time extension to this office for consideration at least one month before that date is reached.
2. You must maintain the activity authorized by this permit in good condition and in conformance with the terms and conditions of this permit. You are not relieved of this requirement if you abandon the permitted activity, although you may make a good faith transfer to a third party, in compliance with General Condition 4 below. Should you wish to cease to maintain the authorized activity or should you desire to abandon it without a good faith transfer, you must obtain a modification of this permit from this office, which may require restoration of the area.
3. If you discover any previously unknown historic or archaeological remains while accomplishing the activity authorized by this permit, you must immediately notify this office of what you have found. We will initiate the Federal and state coordination required to determine if the remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.
4. If you sell the property associated with this permit, you must obtain the signature of the new owner in the attachment provided and forward a copy of the permit to this office to validate the transfer of this authorization.
5. If a conditioned water quality certification has been issued for your project, you must comply with the conditions specified in the certification as special conditions to this permit. For your convenience, a copy of the certification is attached if it contains such conditions. (Condition is not applicable for Section 10 Permits.)
6. You must allow representatives from this office to inspect the authorized activity at any time deemed necessary to ensure that it is being or has been accomplished in accordance with the terms and conditions of your permit.

### **❖ Special Conditions:**

1. This Regional Permit authorizes the discharge of dredged or fill material and other work associated with emergency restoration, repair, or reconstruction measures performed in waters of the United States within the State of Illinois as a result of damages incurred during flooding. Work will be limited to that necessary to restore damaged areas to pre-flood conditions. The time period for completing the proposed work is 180 days from each permit determination.
2. All channel restoration work will be limited to restoring the area to pre-flood conditions and verified using United States Department of Agriculture, Natural Resource Conservation Service, aerial photographs; or other qualifiable data, plans, etc. Channel restoration of areas not caused by the recent flooding, is not authorized under this Regional Permit.
3. Clean, uncontaminated materials must be used for fill in order to minimize excessive turbidity by leaching of fines, as well as to preclude the entrance of deleterious and/or toxic materials into waters of the United States by natural runoff or by leaching. All fill materials must be obtained from upland non-wetland sources or authorized excavation sites. Use of small aggregate materials, such as creek gravel, for stabilization and erosion control is prohibited under this Regional Permit.

4. Temporary levees, cofferdams, accesses, and other fills must involve the least damaging and minimum disturbance or impacts to waters of the United States. Appropriate measures must be taken to maintain near normal downstream flows and to minimize flooding. Fill must be of materials and placed in a manner that will not be eroded by expected high flows. Temporary fill (including sandbags) must be entirely removed to upland non-wetland areas following completion of the construction activity and the affected areas restored to the pre-project conditions. Cofferdams cannot be used to dewater wetlands or other aquatic areas so as to change their use.

5. Any construction debris or waste materials may not be disposed of below the ordinary high water mark of any water body, in a wetland area, or at any location where the material could be introduced into the water body or an adjacent wetland as a result of runoff, flooding, wind, or other natural forces.

6. All dredged or excavated materials, with the exception of that authorized herein, will be placed on an upland site above the ordinary high water line in a confined area, not classified as a wetland, to prevent the return of such material to the waterway.

7. All excavation, dredging, and/or filling in the watercourse must be conducted in a manner that will minimize increases in suspended solids and turbidity which may degrade water quality and damage aquatic life outside the immediate area of operation.

8. All debris during every phase of the project must be immediately removed and properly disposed of in order to prevent accumulation of unsightly, deleterious and/or toxic material in or near the water body.

9. All construction materials, equipment, and/or petroleum products, when not in use, must be stored above anticipated high water levels.

10. All structures will be designed and constructed in such a way that they do not result in stream channel constriction or in redirection of flows in such a way as to cause upstream or downstream erosion, or other property damage.

11. The clearing of timber and other vegetation will be restricted to the absolute minimum required to accomplish the work. The removal of mature trees must be avoided to prevent potential impacts to bald eagle roost sites. To protect the Indiana bat and Northern long-eared bat maternity roosting trees, tree removal will not occur between April 1 through September 30. If tree clearing will be occurring during this time period, the Corps will coordinate further with the United States Fish and Wildlife Services to determine impacts to the Indiana bat and the Northern long-eared bat.

12. Upon completion of earthwork operations, all fills in the water or on shore, and other areas on shore disturbed during construction must be seeded, replanted, or otherwise protected from erosion. The use of crown vetch (*Corinilla varia*), birdfoot trefoil (*Lotus corniculatus*), Canada thistle (*Cirsium arvense*), bull thistle (*Cirsium vulgare*), wild parsnip (*Pastinaca sativa*), common reed (*Phragmites australis*), Eurasian honeysuckles (*Lonicera spp.*), buckthorns (*Rhamnus cathartica* and *R. frangula*), white and yellow sweet clovers (*Melilotus alba* and *M. officinalis*), Japanese Hops (*Humulus japonicus*), canary grass (*Phalaris arundinacea*), purple loosestrife (*Lythrum salicaria*), smooth brome grass (*Bromus inermis*), and switch grass (*Panicum virgatum*) should be avoided. If seeding does not successfully vegetate the disturbed areas by the end of the first growing season, alternate measures, such as placing riprap, slope terracing with untreated railroad ties, gabions or concrete blocks, or additional vegetative plantings to protect the disturbed areas from further erosion must be implemented. You must contact the Corps of Engineers prior to beginning work on any additional erosion control measures so that we can determine if further authorization will be required.

13. Only graded rock, quarry-run rock and/or clean concrete rubble may be used for riprap. The material must be reasonably well graded, consisting of pieces varying in size from 20 pounds up to and including at least some 150-pound pieces. Generally, the maximum weight of any piece should not be more than 500 pounds. Gravel and dirt should not exceed 15 percent of the total fill volume. If concrete rubble is used, all large slabs must be broken to conform to the well-graded requirement. All exposed reinforcement rods, trash, asphalt, and other extraneous materials must be removed before the rubble is placed in waters of the United States

14. All temporary fills, including sand bags, in the waters of the United States must be completely removed within 30 days of the end of the flood emergency and disposed of in accordance with special conditions included in the regional permit.

15. This permit does not authorize construction in any environmentally sensitive area, such as mussel beds, fish spawning areas, waterfowl nesting areas, etc.

16. Measures must be taken for heavy equipment usage in wetland areas to minimize soil disturbance and compaction. All exposed soils and other fills as well as any work below the ordinary high water mark must be permanently stabilized at the earliest practicable date using permanent native vegetation, bioengineering methods, or armoring.

17. Any excavation or placement of temporary or permanent fill must be performed in a way that would not result in the physical destruction of important fish spawning areas, including smothering of downstream spawning areas via turbidity.

18. Petroleum products, other chemicals, and other unsuitable materials (e.g. trash, debris, asphalt, etc.) will be prevented from entering water bodies, streams, and wetlands.

19. Appropriate soil erosion and sediment control measures must be used and maintained during project construction.

20. Temporary and permanent structures must be installed to maintain low flow conditions and to pass normal and expected high flows.

21. The United States shall not be responsible for damage to property or injuries to persons which may arise from or be incident to the work herein authorized, and the permittee shall hold the United States harmless from any and all such claims, except to the extent that the damage or injury is caused solely by the negligence of the United States.

22. The project proponent must notify the appropriate public or private utility in advance of any work within 250 feet of an underground utility so that the utility is not damaged during construction activities.

23. Parties proposing to undertake work under the provisions of these regional permits must provide prior notification to the appropriate Corps of Engineers District. Information submitted by the proponent must clearly determine whether or not the proposed work complies with the conditions and limitations of the regional permit. The proponent will be notified within approximately 15 workdays if the project is in compliance with the conditions of the regional permit and whether project construction may proceed. However, this will not alleviate the need of the proponent to obtain other applicable state or local authorization. The following information is required:

- A completed application form.
- A drawing showing the location and details of the proposed or completed work.
- The information submitted must clearly describe the proposed or completed work.

24. This authorization does not eliminate the requirement that you must still acquire other applicable Federal, state, and local permits. If you have not already coordinated your project with the Illinois Department of Natural Resources – Office of Water Resources, please contact them at 217/782-3863 to determine if a floodplain development permit is required for your project.

25. Applicable general conditions from the standard individual Department of the Army permit will also be included as conditions of these regional permits.

26. **Water quality certification.** By letter dated March 18, 2016, the Illinois Environmental Protection Agency issued Section 401 water quality certification for the regional permit under terms and conditions specified in the Public Notice. These terms and conditions have been incorporated into this regional permit.

27. **Mitigation.** Mitigation may be required on a case-by-case basis for all completed and/or proposed stream or wetland fill activities authorized by this Regional Permit. The following requirements are applicable for projects requiring mitigation:

- a. **Mitigation:** Compensatory mitigation projects provided to offset losses of aquatic resources must follow the regulations published in the Federal Register dated April 10, 2008 under 33 CFR Parts 325 and 332 and 40 CFR Part 230 entitled "Compensatory Mitigation for Losses of Aquatic Resources, Final Rule".
- b. **Mitigation Plan:** A mitigation plan must be submitted to the Corps for approval that includes adequate mitigation acreage to compensate for the loss of any stream or wetland area. A summary of the approved acres and performance measures for the mitigation plan will be incorporated into the Regional Permit as follows:

Mitigation Design Objectives/Performance Measures

Type:	Mitigation					Stream Channel Length (feet)
	Emergent (acres)	Forested (acres)	Open-Water (acres)	Other * (acres)	Total (acres)	
Restoration:						
Creation:						
Enhancement:						
Preservation:						
Total:						

\* Replace "Other" with actual type of mitigation ("Upland", "Woodland", etc.)

If excavation and construction are completed outside an optimal seeding period, temporary erosion control protection shall be implemented immediately upon completion of excavation and construction and shall be maintained until such time as wetland or riparian plantings can be completed during an optimal period. The permanent wetland plantings shall then be completed during the next optimal seeding period.

In addition:

- The boundaries of the mitigation sites shall be identified clearly by the placement of permanent boundary markers.
- An as-built plan shall be submitted to the Corps of Engineers upon project completion.

- Any future development or land-use conversion of the mitigation area for any purpose which may interfere with or be detrimental to functions is prohibited without prior written approval from the Corps of Engineers.
- c. Mitigation Monitoring.
- Mitigation work shall begin concurrent with the initiation of project construction. The mitigation work shall be completed within one year of the initiation of project construction on the site.
  - The permittee shall notify this office in writing upon the completion of the mitigation plan. The permittee shall be responsible to perform any corrective actions deemed necessary by this district to insure success.
- d. Reporting. The permittee shall provide an annual report to the Corps of Engineers documenting the extent of the mitigation completed.
- The permittee shall conduct an annual survey of the mitigation area to monitor the survival rate of the plantings, and soil and hydrology conditions at the site. The results of the survey will be documented annually on the Rock Island District Standard Mitigation Reporting Form also available at: <http://www.mvr.usace.army.mil/Missions/Regulatory.aspx> or in an annual progress report as specified in RGL 08-03, <http://www.mvr.usace.army.mil/Missions/Regulatory/WetlandMitigation.aspx>. These annual reports are due no later than August 31 of each year for the 5-year period. All annual monitoring reports shall be formatted for an 8.5 x 11 inch piece of paper. The mitigation monitoring reports shall be submitted to the Corps of Engineers. Reports are due as follows:
    - o Year 1 – due August 31 – 1 year after construction is initiated
    - o Years 2 through 5 – due of each succeeding year
  - These reports shall include the following information at a minimum:
    - o Data point(s) collected utilizing the Wetland Determination Data Form for the appropriate region, typically Midwest, from the US Army Corps of Engineers
    - o Information concerning the survival rate of all plant species which were to be established at the mitigation site. This information shall be collected by a qualified biologist.
    - o Annual photographs (taken during the growing season) showing representative areas of the site.
    - o Additional guidance on the monitoring reports may be found in the Regulatory Guidance Letter 08-03 dated October 10, 2008.
    - o Vegetative cover map indicating dominant cover species in each area.
    - o Plant, soil, and hydrology assessment utilizing the procedures in the following documents:
      - *Wetlands Research Program Technical Report Y-87-1 Corps of Engineers Wetlands Delineation Manual, January 1987.*
      - *Interim Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region, September 2008.*
    - o Monthly surface water elevations at the site.
- e. Survival of plantings. All newly planted trees and emergent plant species will be guaranteed for 85 percent survival for five growing seasons. Any newly planted tree or shrub (including replacements), which dies to the point that the main leader has died back or where there is 25 percent or more of the crown dead, will be replaced. All replacements will be of the same species

and size and of equal wildlife value and function as originally planted. Damages incurred in making replacements will be repaired.

- f. **Liability.** The permittee shall assume all liability for accomplishing any needed corrective work should the District Engineer determine that the mitigation is not satisfactory. Remedial work may include regrading and/or replanting the mitigation site. This responsibility shall extend for a period of 5 years upon completion of the mitigation work. The permittee shall take immediate proactive steps necessary to correct any deficiencies outlined in the monitoring reports and shall coordinate with this office during implementation to insure compliance with the terms and conditions in this permit.
- g. **Financial Assurances.** A description of financial assurances (bonds, escrow accounts, etc.) that will be provided and how they are sufficient to ensure a high level of confidence that the compensatory mitigation project will be successfully completed in accordance with its performance standards (33 CFR 230.93(n)).
- h. Your responsibility to complete the required compensatory mitigation will not be considered fulfilled until you have demonstrated mitigation success and have received written verification from the U.S. Army Corps of Engineers:

<<<<<    **END OF SPECIAL CONDITIONS**    >>>>>

**Further information:**

1. **Congressional Authorities:** You have been authorized to undertake the activity described above pursuant to:

- ( X ) Section 10 of the Rivers and Harbors Act of 1899 (33 U.S.C. 403).
- ( X ) Section 404 of the Clean Water Act (33 U.S.C. 1344).
- ( ) Section 103 of the Marine Protection, Research and Sanctuaries Act of 1972 (33 U.S.C. 1413).

2. **Limits of this authorization.**

- a. This permit does not obviate the need to obtain other Federal, state, or local authorizations required by law.
- b. This permit does not grant any property rights or exclusive privileges.
- c. This permit does not authorize any injury to the property or rights of others.
- d. This permit does not authorize interference with any existing or proposed Federal project.

3. **Limits of Federal Liability.** In issuing this permit, the Federal Government does not assume any liability for the following:

- a. Damages to the permitted project or uses thereof as a result of other permitted or unpermitted activities or from natural causes.
- b. Damages to the permitted project or uses thereof as a result of current or future activities undertaken by or on behalf of the United States in the public interest.
- c. Damages to persons, property, or to other permitted or unpermitted activities or structures caused by the activity authorized by this permit.
- d. Design or construction deficiencies associated with the permitted work.
- e. Damage claims associated with any future modification, suspension, or revocation of this permit.

4. **Reliance on Applicant's Data.** The determination of this office that issuance of this permit is not contrary to the public interest was made in reliance on the information you provided.

5. **Reevaluation of Permit Decision.** This office may reevaluate its decision on this permit at any time the circumstances warrant. Circumstances that could require a reevaluation include, but are not limited to, the following:

- a. You fail to comply with the terms and conditions of this permit.
- b. The information provided by you in support of your permit application proves to have been false, incomplete, or inaccurate (See 4 above).
- c. Significant new information surfaces which this office did not consider in reaching the original public interest decision.



Such a reevaluation may result in a determination that it is appropriate to use the suspension, modification, and revocation procedures contained in 33 CFR 325.7 or enforcement procedures such as those contained in 33 CFR 326.4 and 326.5. The referenced enforcement procedures provide for the issuance of an administrative order requiring you to comply with the terms and conditions of your permit and for the initiation of legal action where appropriate. You will be required to pay for any corrective measures ordered by this office, and if you fail to comply with such directive, this office may in certain situations (such as those specified in 33 CFR 209.170) accomplish the corrective measures by contract or otherwise and bill you for the cost.

**6. Extensions.** General condition 1 establishes a time limit for the completion of the activity authorized by this permit. Unless there are circumstances requiring either a prompt completion of the authorized activity or a reevaluation of the public interest decision, the Corps will normally give favorable consideration to a request for an extension of this time limit.

This permit becomes effective when the Federal official, designated to act for the Secretary of the Army, has signed below.

*Robert S. Gramke*

Robert S. Gramke  
Chief, Regulatory Branch  
US Army Corps of Engineers - St. Louis District

When the structures or work authorized by this permit are still in existence at the time the property is transferred, the terms and conditions of this permit will continue to be binding on the new owner(s) of the property. To validate the transfer of this permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below.

\_\_\_\_\_

Transferee

\_\_\_\_\_

Date



## ILLINOIS ENVIRONMENTAL PROTECTION AGENCY

1021 NORTH GRAND AVENUE EAST, P.O. BOX 19276, SPRINGFIELD, ILLINOIS 62794-9276 • (217) 782-3397

BRUCE RAUNER, GOVERNOR

LISA BONNETT, DIRECTOR

217/782-3362

**MAR 18 2016**

U.S. Army Corps of Engineers, Rock Island District  
ATTN: Regulatory Branch  
Clock Tower Building  
Post Office Box 2004  
Rock Island, IL 61204-2004

Re: U.S. Army Corps of Engineers (Various Counties)  
Re-issuance of Regional Permit 26 - Various Waterbodies  
Log # C-0600-15 [CoE appl. # CEMVR-OD-P-2015-965]

Gentlemen:

This Agency received and reviewed the December 8, 2015 public notice regarding the U.S. Army Corps of Engineers Regional Permit 26 for emergency repairs and construction related to flood damage that has or will occur in those counties in Illinois declared disaster areas.

Section 401 water quality certification is hereby issued for this regional permit, under the terms and conditions specified in the Public notice received by the Agency on December 3, 2015 and the draft permit received on January 20, 2016.

If you have any questions concerning this matter, please contact Darren Gove at 217/782-3362.

Sincerely,

Alan Keller, P.E.  
Manager, Permit Section  
Division of Water Pollution Control

SAK:DLH:DRG:C-0600-15\_401 WQ Certification\_20Nov15.docx

cc: IEPA, Records Unit  
IEPA, DWPC, FOS, All regions  
IDNR, OWR, Springfield  
USEPA, Region 5  
CoE, St. Louis District  
CoE, Chicago District  
CoE, Memphis District  
CoE, Louisville District  
CoE, Louisville District (Newburg Regulatory Office)

IEPA Log No.: C-0600-15  
CoE appl. #: CEMVR-OD-P-2015-965

Public Notice Beginning Date: February 1, 2016  
Public Notice Ending Date: February 22, 2016

Section 401 of the Federal Water Pollution Control Act  
Amendments of 1972

**Section 401 Water Quality Certification to Discharge into Waters of the State**

**Public Notice/Fact Sheet Issued By:**

Illinois Environmental Protection Agency  
Bureau of Water  
Permit Section  
1021 North Grand Avenue East  
Post Office Box 19276  
Springfield, Illinois 62794-9276  
217/782-3362

**Name and Address of Discharger:** U.S. Army Corps of Engineers, Rock Island District – Clock Tower Building, P.O. Box 2004, Rock Island, IL 61204-2004

**Discharge Location:** Near in of Township , Range of the P.M. in All Illinois Counties County.

**Name of Receiving Water:** Waters of the State

**Project Description:** Proposed re-issuance of Regional Permit 26 for the emergency reconstruction and repair activities for flood damaged areas.

The Illinois Environmental Protection Agency (IEPA) has received an application for a Section 401 water quality certification to discharge into the waters of the state associated with a Section 404 permit application received by the U.S. Army Corps of Engineers. The Public Notice period will begin and end on the dates indicated in the heading of this Public Notice. The last day comments will be received will be on the Public Notice period ending date unless a commenter demonstrating the need for additional time requests an extension to this comment period and the request is granted by the IEPA. Interested persons are invited to submit written comments on the project to the IEPA at the above address. Commenters shall provide their names and addresses along with comments on the certification application. Commenters may include a request for public hearing. The certification and notice number(s) must appear on each comment page.

The attached Fact Sheet provides a description of the project and the antidegradation assessment.

The application, Public Notice/Fact Sheet, comments received, and other documents are available for inspection and may be copied at the IEPA at the address shown above between 9:30 a.m. and 3:30 p.m. Monday through Friday when scheduled by the interested person.

If written comments or requests indicate a significant degree of public interest in the certification application, the IEPA may, at its discretion, hold a public hearing. Public notice will be given 30 days before any public hearing. If a Section 401 water quality certification is issued, response to relevant comments will be provided at the time of the certification. For further information, please call Darren Gove at 217/782-3362.

DRG:C-0600-15\_401 PN and FS\_20Nov15(2).docx

Fact Sheet for Antidegradation Assessment  
For U.S. Army Corps of Engineers, Rock Island District  
IEPA Log No. C-0600-15  
COE Log No. CEMVR-OD-P-2015-965  
Contact: Brian Koch (217) 785-4116  
Public Notice Start Date: February 1, 2016

---

The U.S. Army Corps of Engineers, Rock Island District (USACE) has proposed re-issuance of Regional General Permit 26 that will authorize work in waters of the United States, including rivers, lakes, streams, and wetland areas, associated with emergency reconstruction and repair activities in counties declared flood disaster areas by the State of Illinois.

This regional permit will authorize the following emergency protection and repair measures that are not exempted or already authorized by Nationwide, Regional, or Individual permits:

- a. Repair of levees to existing elevations and cross-section, including breach closures and borrow operations.
- b. Bridge embankment protection (armoring) or repair.
- c. Repair of pre-existing highway or railroad embankments and the addition or repair of stone (armoring) protection.
- d. Repair of pre-existing utility protection structures.
- e. Placement of rock and/or earth materials for stream/ditch bank protection and/or stream/ditch bank restoration.
- f. Drainage ditch restoration to pre-flood capacity and flow line unless the flow line must be altered due to other damage associated with the flood event.
- g. Restoration of creek channels to pre-flooding alignment and capacity.
- h. Construction of temporary haul roads to facilitate the completion of any of the listed activities.

Special conditions have also been proposed in this regional permit that: limit the restoration of the project to pre-flood conditions; require clean, uncontaminated materials for fill; require appropriate guidelines for the use of temporary levees, accesses and fills; require that all dredged or excavated materials be placed on upland, non-wetland sites; require work to be conducted in a manner to minimize increases in suspended solids and turbidity; require appropriate guidelines for the use and storage of petroleum products; regulate the design and construction of stream channels to minimize erosion and property damage; restrict tree clearing between April 1 through September 30 for protection of endangered bats; prohibit the use of various plant species for vegetative cover; specify the type and size of rock to be utilized; require consultation with Illinois Department of Natural Resources and require acquisition of applicable federal, state, and local permits; and specify wetland mitigation design objectives and performance measures, among others.

#### **Identification and Characterization of the Affected Water Body**

The Regional General Permit No. 26 may be applied to those water bodies that are General Use waters within the State of Illinois.

### **Identification of Proposed Pollutant Load Increases or Potential Impacts on Uses**

Activities that would be authorized under the proposed permit may result in short-term, minor impacts to the waterbody. They are unlikely to result in a change in the existing uses of a water body.

### **Purpose and Anticipated Benefits of the Proposed Activity**

Projects authorized under the proposed permit will reconstruct and/or repair areas affected by floods in counties declared flood disaster areas by the State of Illinois.

### **Assessment of Alternatives for Less Increase in Loading or Minimal Environment Degradation**

The assessment of the activities allowed under this permit finds that the general and special conditions and limitations as defined by the proposed permit would assure that the projects would be completed in a manner that minimizes environmental degradation.

### **Agency Conclusion**

This preliminary assessment was conducted pursuant to the Illinois Pollution Control Board regulation for Antidegradation found at 35 Ill. Adm. Code 302.105 (antidegradation standard) and was based on the information available to the Agency at the time the assessment was written. We tentatively find that the Regional Permit 26 proposed for general 401 Water Quality Certification, with applicable special conditions, would have minimal individual and cumulative impacts on the aquatic resources within the State of Illinois. These activities are therefore compliant with the Antidegradation standard and no further evaluation under 35 Ill. Adm. Code 302.105 (Antidegradation standard) will be required. Comments received during the 401 Water Quality Certification public notice period will be evaluated before a final decision is made by the Agency.